



Linda M. Hodgdon
Commissioner

STATE of NEW HAMPSHIRE
DEPARTMENT of ADMINISTRATIVE SERVICES
BUREAU of PUBLIC WORKS - DESIGN & CONSTRUCTION
POB 483, 7 Hazen Drive – Room 250
Concord, New Hampshire 03302-0483
Phone 603-271-3516, Fax 603-271-3515

ADDENDUM NUMBER 01

FOR

REPAIR STEPS, RETAINING WALL AND WALKWAYS

STATEWIDE

NEW HAMPSHIRE

BUREAU OF COURT FACILITIES

BUREAU OF PUBLIC WORKS PROJECT NUMBER 80452R

CONTRACT A

MARCH 20, 2009

DOCUMENT 00911

ADDENDUM NUMBER 01

TO: ALL CONTRACT BIDDERS OF RECORD

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated March 10, 2009, with amendments and additions noted below.

Acknowledge receipt of this Addendum in the space provided in the Proposal Form. Failure to do so may disqualify the Bidder.

This Addendum consists of 4 pages and the following Drawings:

No.	Drawing Title	Issue Date
S-2a	Lancaster Site Plan Addendum 1	3/20/09

CHANGES TO THE SPECIFICATIONS

DOCUMENT 00416 – PROPOSAL FORM

1. Item #5: Change the amount of Allowance from \$6,000.00 to \$16,000.00.

SECTION 01200 – PRICE AND PAYMENT PROCEDURES

2. Article 1.2 Paragraph A: Change the amount of Allowance from \$15,750.00 to \$16,000.00.

SECTION 01500 – TEMPORARY FACILITIES AND CONTROLS

3. Add the following article:

PROJECT IDENTIFICATION

- A. Project Identification Sign:
 1. One painted sign at each location of construction and design as shown in sample attached to end of specification section. One painted sign, 32 sq ft (3 sq m) area, bottom 6 feet (2 m) above ground.
 2. Content: Specific information to be determined after Award of Contract.
 - a. Project number, title, logo and name of State Entity as indicated on Contract Documents.
 - b. Names Commissioner and Governor.
 - c. Names and titles of Architect/Engineer and Consultants.
 - d. Name of Prime Contractor.
 - e. Contract Amount.
 - f. Legislation that authorized project.
 3. Graphic Design, Colors, Style of Lettering: As shown in attached sample at end of specification section.
 4. Lettering: Typeface – Times New Roman, Univers, Arial or CG Omega.

- B. Project Informational Signs:
1. Painted informational signs of same colors and lettering as Project Identification sign, or standard products; size lettering for legibility at 100 feet (30 m) distance.
 2. Provide signs on location as directed by Contract Administrator. Relocate as Work progress requires.
 3. Provide municipal agency directional traffic signs to and within site.
 4. No other signs are allowed without State permission except those required by law.
- C. Design sign and structure to withstand 60 miles/hr (100 km/hr) wind velocity.
- D. Sign Painter: Experienced as professional sign painter for minimum three years.
- E. Finishes, Painting: Adequate to withstand weathering, fading, and chipping for duration of construction.
- F. Show content, layout, lettering, color.
- G. Sign Materials:
1. Structure and Framing: New, wood, structurally adequate.
 2. Sign Surfaces: Exterior grade plywood with medium density overlay, minimum 3/4 inches (19 mm) thick, standard large sizes to minimize joints.
 3. Rough Hardware: Galvanized.
 4. Paint and Primers: Exterior quality, two coats; sign background of white color.
 5. Lettering: Exterior quality paint, black color.
- ***** [OR] *****
6. Lettering: Pre-cut vinyl self-adhesive products, black.
- H. Installation:
1. Install project identification sign prior to start of construction.
 2. Erect at designated location.
 3. Erect supports and framing on secure foundation, rigidly braced and framed to resist wind loadings.
 4. Install sign surface plumb and level, with butt joints. Anchor securely.
 5. Paint exposed surfaces of sign, supports, and framing.
- I. Maintenance: Maintain signs and supports clean, repair deterioration and damage.
- J. Removal: Remove signs, framing, supports, and foundations at completion of Project and restore area.

CHANGES TO THE DRAWINGS

DRAWING S-1 – LEBANON SITE PLAN AND DETAILS

4. Clarification – Existing handrails are to be removed and replaced with new handrails according to Construction Notes. Color to be changed from black to gray.

DRAWING S-2 – LANCASTER SITE PLAN AND DETAILS

5. Replace “Site Plan” portion of drawing with S-2a LANCASTER SITE PLAN ADDENDUM 1.
Clarification – Access ramps are included in reconstruction. Number and location of accessibility ramps to remain as existing.



Michelle L. Juliano, P.E., Assistant Administrator
Bureau of Public Works Design and Construction

END OF DOCUMENT

EXISTING BUILDING

SHOT BLAST CONCRETE
UNDER CANOPY TO ACHIEVE
A SLIP RESISTANT FINISH
(PROTECT ADJACENT SURFACES)

RAMP

EXISTING RAMP
TO REMAIN

EXISTING RAMP
TO REMAIN

EXISTING RAMP
TO REMAIN

LIMITS OF SIDEWALK
REPLACEMENT



PLAN NORTH

NOTES:

1. ALIGN NEW SIDEWALK WITH EXISTING TO PROVIDE A SMOOTH TRANSITION.
2. REPLACE ALL DISTURBED LOAM AND RESEED AREAS EFFECTED BY CONSTRUCTION.



**Bureau of Public Works
Design and Construction**
Seven Hazen Drive
Concord, NH 03302
Tel. (603) 271-3516
Fax. (603) 271-3515

REPAIR STEPS, RETAINING WALL AND WALKWAYS STATEWIDE

LANCASTER SITE PLAN ADDENDUM 1

DRAWN BY: JAF

SCALE: NONE

DATE: 3/20/09

PROJECT No.
80452R
CONTRACT A

S-2a
REVISION: