



Linda M. Hodgdon
Commissioner

STATE of NEW HAMPSHIRE
DEPARTMENT of ADMINISTRATIVE SERVICES
BUREAU of PUBLIC WORKS - DESIGN & CONSTRUCTION
POB 483, 7 Hazen Drive - Room 250
Concord, New Hampshire 03302-0483
Phone 603-271-3516, Fax 603-271-3515

ADDENDUM NUMBER 03

Emergency Generator Upgrades; N. H. Dept. of Safety

33 Hazen Drive

Concord, NH

Department of Safety

Bureau of Public Works Project Number 80599R

Contract A

August 9, 2011

DOCUMENT 00913

ADDENDUM NUMBER 03

TO: ALL CONTRACT BIDDERS OF RECORD


This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated July 14, 2011, Addendum Number 1 issued July 21, 2011, and Addendum Number 2 issued August 2, 2011, with amendments and additions noted below.

Acknowledge receipt of this Addendum in the space provided in the Proposal Form. Failure to do so may disqualify the Bidder.

This Addendum consists of two (2) pages including the cover sheet:

GENERAL CHANGES AND INFORMATION

1. The two feeders designated as "K" and "A" on the drawings are each approximately 100 feet in length. They will enter into the building basement near the stairway at the south end of the building directly in the area in back of the generator location. The conduits will then immediately make a 90 degree turn and run to the elevator lobby and make another turn into the new electric room. In this way they can be run to the new electric room in a manner that will avoid going through the water service room and elevator shaft. The "K" feeder will terminate in the Distribution box shown on the drawings to feed the two 600 amp transfer switches. The A feeder will terminate in the new 100 amp ATS that feeds Panel LS-A1.
2. The two generators in the basement and the larger generator in the gray enclosure outside the building are Natural Gas fired. The small 45 KW generator in the green enclosure is fueled by the LP gas tank.
3. The conduits running from the new generator to the building do not have to be concrete encased.
4. The LP gas tank to be removed is 1000-gallon capacity. The Propane vendor is Energy North.


for Mark T. Nogueira, P.E.
Administrator – Bureau of Public Works

END OF DOCUMENT