



Information Report

HARTS LOCATION-CARROLL

26162

X-A003(275)

County:	CARROLL, COOS
Date Bids Open:	8/31/2017
Scope of Work:	Rehabilitate a 925 ft variable cross section metal culvert
Location:	US 302
Completion Date:	10/5/2018
Proposal Guarantee:	5% of bid amount

HARTS LOCATION-CARROLL 26162			
Item Number	Item Description	Unit	Estimated Quantity
Culvert			
206.19	COMMON STRUCTURE EXCAVATION EXPLORATORY	CY	10.00
503.101	WATER DIVERSION STRUCTURE	U	1.00
512.02	PREPARATION FOR CONCRETE REPAIRS, CLASS II	SY	1.00
520.01	CONCRETE CLASS AA	CY	1.00
520.1	CONCRETE CLASS A	CY	5.00
568.	STRUCTURAL TIMBER (F)	MBM	1.90
571.1	REPAIRING AND POINTING STONE MASONRY	SY	7.00
602.011	FILL MATERIAL FOR ANNULAR SPACE	CY	310.00
602.24201	METAL STRUCTURAL PLATE LINER FOR ARCH PIPE	LF	600.00
602.73101	GEOPOLYMER REINFORCED MORTAR SPRAY-ON LINER FOR ARCH PIPE	LF	325.00
602.73201	GEOPOLYMER NON-STRUCTURAL MORTAR SPRAY-ON LINER FOR ARCH PIPE	LF	20.00
618.61	UNIFORMED OFFICERS WITH VEHICLE	\$	6,000.00
618.7	FLAGGERS	HR	600.00
619.1	MAINTENANCE OF TRAFFIC	U	0.60
619.25	PORTABLE CHANGEABLE MESSAGE SIGN	U	1.50

619.279	AUTOMATED TRAILER-MOUNTED SPEED LIMIT SIGN	U	2.00
645.512	COMPOST SOCK FOR PERIMETER BERM	LF	450.00
645.531	SILT FENCE	LF	450.00
645.7	STORM WATER POLLUTION PREVENTION PLAN	U	0.80
645.71	MONITORING SWPPP AND EROSION AND SEDIMENT CONTROLS	HR	200.00
692.	MOBILIZATION	U	0.75
698.13	FIELD OFFICE TYPE C	MON	4.00
699.	MISCELLANEOUS TEMPORARY EROSION AND SEDIMENT CONTROL	\$	5,000.00
1010.15	FUEL ADJUSTMENT	\$	15,000.00

Rock

203.91	ROCK SCALING - HAND METHOD	HR	320.00
225.2	PRESTRESSED ROCK BOLTS	LF	180.00
606.417	PORTABLE CONCRETE BARRIER FOR TRAFFIC CONTROL	LF	1,200.00
606.9523	TEMP. IMPACT ATTENUATION DEVICE (NON-REDIRECTIVE) TEST LEVEL 3	U	2.00
616.171	PORTABLE TRAFFIC SIGNALS (PTS) SYSTEM	U	1.00
618.61	UNIFORMED OFFICERS WITH VEHICLE	\$	6,000.00
618.7	FLAGGERS	HR	200.00
619.1	MAINTENANCE OF TRAFFIC	U	0.40
619.25	PORTABLE CHANGEABLE MESSAGE SIGN	U	0.50
632.1104	PREFORMED RETROREFLECTIVE TAPE, TYPE I (REMOVABLE) 4" LINE	LF	500.00
632.1118	PREFORMED RETROREFLECTIVE TAPE, TYPE I (REMOVABLE) 18" LINE	LF	30.00
632.1306	BLACKOUT PAVEMENT MARKING TAPE, TYPE I (REMOVABLE), 6" LINE	LF	1,150.00
645.7	STORM WATER POLLUTION PREVENTION PLAN	U	0.20
645.71	MONITORING SWPPP AND EROSION AND SEDIMENT CONTROLS	HR	20.00
670.104	TEMPORARY PORTABLE LIGHTING	U	2.00
692.	MOBILIZATION	U	0.25
698.13	FIELD OFFICE TYPE C	MON	2.00

699.	MISCELLANEOUS TEMPORARY EROSION AND SEDIMENT CONTROL	\$	1,500.00
1010.15	FUEL ADJUSTMENT	\$	5,000.00