

**STATE OF NEW HAMPSHIRE**  
**DEPARTMENT OF TRANSPORTATION**

**STATEWIDE 28137**  
**STATEWIDE 28138**


September 24, 2015

**ADDENDUM NO. 1**

Bidders are hereby advised to make the following revisions to the Proposal and Plans:

1. **Replace**, in the Proposal, page 28 with attached page 28A, which is the **Summary of Environmental Issues**.

**THE CONTRACTOR SHALL ACKNOWLEDGE THIS**  
**ADDENDUM ON THE BID ENVELOPE**

  
\_\_\_\_\_  
Christopher M. Waszczuk, P. E.  
Director of Project Development

  
\_\_\_\_\_  
Date

## **Summary of Environmental Issues**

*The Following is provided to assist in identifying the environmentally sensitive aspects of this project. This notification is neither intended to be all-inclusive nor to replace the need to thoroughly read and abide by all contract documents including but not limited to all applicable state specifications and permits.*

### **Actions to be completed prior to construction**

- All work shall be located within the existing State right-of-way or easements. Should the scope of work change to extend beyond the existing State right-of-way or easements, or involve any ground disturbance in previously undisturbed areas, the Bureau of Environment shall be contacted prior to the commencement of construction.
- There is no permit required for the work as proposed. Should the Contractor's method of construction require work within areas under NH Department of Environmental Services Wetlands Bureau jurisdiction, the Contractor shall obtain all necessary permits from the Wetlands Bureau and the US Army Corps of Engineers prior to the commencement of work. Permit applications shall be reviewed by the Bureau of Environment and the Bureau of Construction prior to submission to the Wetlands Bureau.
- If the Contractor's method of construction require excavation beyond that required for removing or installing a U-post sign, further coordination with the Bureau of Environment shall be required prior to the commencement of construction.
- All appropriate erosion and stormwater management measures shall be installed prior to the commencement of work. Such measures shall be inspected and maintained throughout construction.

### **Actions to be completed during construction**

- All work, including access, staging and vehicle parking, shall be located on paved or gravel surfaces, or maintained vegetated areas. In all instances, such areas shall be dry and firm enough to support all equipment.
- Access to all properties shall be maintained throughout construction.
- The project area has not been reviewed for invasive plant species. In order to avoid the potential spread of invasive plants, all vegetation that is cut as a result of the proposed work shall remain on site.
- No trees larger than 3" diameter at breast height shall be cleared without additional coordination with the Bureau of Environment.