

**STATE OF NEW HAMPSHIRE
DEPARTMENT OF TRANSPORTATION**

**CANAAN
28335**


September 24, 2015

ADDENDUM NO. 1

Bidders are advised to make the following revision to the Proposal:

1. **Revise**, in the Proposal, on page 11, in the Prosecution of Work, in the **CONSTRUCTION REQUIREMENTS** section, Bridge Deck subsection, Note 2, to read as follows:
 2. The screed used during deck pouring operations shall not be supported on any stringer partially loaded from the existing deck or deck placed in a previous phase. In addition, the bay between any partially loaded beam and the nearest unloaded beam shall be screeded independently of the portion of deck utilizing the screed. **The screed does not have to be self-propelled nor must it be equipped with an auger. Hand screeding will not be allowed.** No additional costs associated with this requirement will be considered.

**THE CONTRACTOR SHALL ACKNOWLEDGE THIS
ADDENDUM ON THE BID ENVELOPE**



Christopher M. Waszczuk, P. E.
Director of Project Development



Date