

County: STRAFFORD

Date Bids Open: 7/21/2016

Scope of Work: Guardrail & end unit replacement along the Spaulding Turnpike

Location: Spaulding Turnpike (NH 16)

Completion Date: 6/30/2017

Proposal Guarantee: 5% of bid amount

Item Number	Item Description	Unit	Estimated Quantity
ROCHESTER-MILTON 40040			
Road way			
202.7	REMOVAL OF GUARDRAIL	LF	18,000.00
203.55543	GUARDRAIL EAGRT OFFSET PLATFORM, TL 3	U	31.00
203.601	EMBANKMENT-IN-PLACE	CY	2,300.00
206.19	COMMON STRUCTURE EXCAVATION EXPLORATORY	CY	25.00
304.32	CRUSHED GRAVEL FOR SHOULDER LEVELING	TON	870.00
565.222	BRIDGE APPROACH RAIL T2 (STEEL POSTS)	U	4.00
565.802	ADJUSTING BRIDGE APPROACH RAIL	U	16.00
606.1254	BEAM GUARDRAIL (TERMINAL UNIT TYPE EAGRT, TL 3) (STEEL POST)	U	31.00
606.127	BEAM GUARDRAIL (TERMINAL UNIT TYPE G-2) (STEEL POST)	U	7.00
606.18001	31" W-BEAM GUARDRAIL WITH 8" OFFSET BLOCK (STEEL POST)	LF	18,500.00
609.811	BITUMINOUS CURB, TYPE B (4" REVEAL)	LF	11,800.00
618.61	UNIFORMED OFFICERS WITH VEHICLE	\$	25,000.00
619.1	MAINTENANCE OF TRAFFIC	U	1.00
619.25	PORTABLE CHANGEABLE MESSAGE SIGN	U	2.00
619.63	TRUCK-MOUNTED IMPACT ATTENUATOR, TEST LEVEL 3	U	2.00

621.2	RETROREFLECTIVE BEAM GUARDRAIL DELINEATOR	EA	200.00
621.31	SINGLE DELINEATOR WITH POST	EA	100.00
645.531	SILT FENCE	LF	3,300.00
646.41	TURF ESTABLISHMENT WITH MULCH, TACKIFIERS AND HUMUS	SY	6,500.00
692.	MOBILIZATION	U	1.00
699.	MISCELLANEOUS TEMPORARY EROSION AND SEDIMENT CONTROL	\$	5,000.00
1008.11	ALTERATIONS AND ADDITIONS AS NEEDED - UNANTICIPATED WORK	\$	25,000.00
1010.15	FUEL ADJUSTMENT	\$	10,000.00