

2/9/2000

1 of 1

Supersedes Suppl. Spec. Dated 9/16/98

S U P P L E M E N T A L S P E C I F I C A T I O N
AMENDMENT TO SECTION 201 -- CLEARING AND GRUBBING

Amend the Description to read:

1.1 This work shall consist of clearing and grubbing within the limits shown on the plans or as ordered, except objects designated to be removed in accordance with other sections of these Specifications. Vegetation and objects designated or ordered to remain shall be preserved from injury or damage.

1.2 This work shall also consist of clearing and grubbing areas of brush within the project limits, but outside the limits of clearing and grubbing shown on the plans.

1.3 The items of removing trees, pruning trees, removing stumps, roadside clean up, and selective clearing and thinning will be used for work performed outside of the areas designated under 1.1 and 1.2.

1.4 Definitions:

(a) Clearing. Cutting, removing and disposing of all trees, logs, brush, debris and vegetation within a designated area.

(b) Grubbing. Removing and disposing of all stumps and roots within a designated area.

(c) Large Tree. Tree measuring in circumference 1.9 m (75 in) and over at a point 1.2 m (4 ft) above the average ground.

(d) Small Tree. Tree measuring in circumference less than 1.9 m (75 in) but more than 300 mm (12 in) at a point 1.2 m (4 ft) above the average ground.

(e) Brush. Area of growth including grass, weeds, crops and trees measuring in circumference 300 mm (12 in) or less at a point 1.2 m (4 ft) above the average ground.

Amend 4.1 to read:

4.1 Clearing, grubbing, and clearing and grubbing will not be measured, but shall be the hectare (acre) final pay quantity in accordance with 109.11 for the area(s) shown on the plans.

Amend 4.1.1 to read:

4.1.1 Clearing for fence lines will not be measured, but shall be the hectare (acre) final pay quantity in accordance with 109.11 for the area(s) shown on the plans.

Amend 4.2 to read:

4.2 Trees will be measured by the number of trees of each size removed or pruned.

Delete 4.2.1

Delete 4.2.2

Amend 4.3 to read:

4.3 Stumps will be measured by the number of stumps removed measuring more than 300 mm (12 in) in circumference at the cutoff. Stumps of trees cut by the Contractor will not be measured.

Add to Method of Measurement:

4.5 Selective clearing and thinning will not be measured, but shall be the hectare (acre) final pay quantity in accordance with 109.11 for the area(s) shown on the plans

Amend 5.1 to read:

5.1 Clearing, grubbing, and clearing and grubbing are final pay quantity items and will be paid for at the contract unit prices per hectare (acre) in accordance with 109.11.

Amend 5.1.2 to read:

5.1.2 Clearing for fence lines is a final pay quantity item and will be paid for at the contract unit price per hectare (acre) in accordance with 109.11.

Add to 5.1:

5.1.3 When no quantity for clearing for fence lines is included in the contract, the work will be subsidiary.

5.1.4 Clearing and grubbing in areas of brush within the project limits, but outside the limits shown on the plans will be subsidiary.

Amend 5.2 to read:

5.2 The accepted quantities of removed trees and their stumps will be paid for at the contract unit price per each of the size of tree specified.

Amend 5.2.4 to read:

5.2.4 When no quantity for large trees and their stumps is included in the contract, the removal of large trees and their stumps will be paid for as provided in 109.04.

5.2.4.1 When no quantity for small trees and their stumps is included in the contract, the removal of small trees and their stumps will be subsidiary.

Amend 5.3.1 to read:

5.3.1 When no quantity of stumps is included in the contract, the removal of stumps will be subsidiary.

Add to Basis of Payment:

5.6 Selective clearing and thinning is a final pay quantity item and will be paid at the contract unit price per hectare (acre) in accordance with 109.11.

Amend the following Pay items and units:

201.01	Clearing (F)	Hectare (Acre)
201.02	Grubbing (F)	Hectare (Acre)
201.1	Clearing and Grubbing (F)	Hectare (Acre)
201.6	Clearing for Fence Lines (F)	Hectare (Acre)
201.7	Selective Clearing and Thinning (F)	Hectare (Acre)