SUPPLEMENTAL SPECIFICATION

AMENDMENT TO SECTION 699 -- TEMPORARY PROJECT EROSION AND WATER POLLUTION CONTROL

Description

Amend 1.1 to read:

1.1 This work shall consist of temporary measures necessary to control erosion and prevent water pollution through the life of the contract. This work includes but is not necessarily limited to the use of pipes, berms, dams, sediment basins, fiber mats, filter fabrics, netting, gravel, slope drains and other erosion control devices or methods.

Amend 1.2 to read:

1.2 The temporary erosion and pollution control provisions contained herein shall be coordinated with the permanent erosion control features specified elsewhere in the contract to the extent practicable to ensure economical, effective and continuous erosion control throughout the construction and post construction periods.

<u>Delete</u> 2.1:

Amend 2.2 to read:

2.1 Temporary slope drains may be constructed of rigid or flexible pipe, fiber mats, rubble, concrete or bituminous sluices, plastic sheets or other acceptable material that will protect slopes from erosion.

<u>Delete</u> 2.3:

Amend 2.4 to read:

2.2 Fertilizer and soil conditioners shall be an acceptable standard commercial grade.

Delete 2.5:

Amend 3.1 to read:

3.1 Construction requirements shall be as specified in 645.3 and as directed.

Amend 3.1.1 to read:

3.2 No work requiring erosion control shall commence until the Erosion and Sediment Control and Stormwater Management Plan has been approved by the Engineer.

<u>Delete</u> remaining Construction requirements:

Amend 4.1 to read:

4.1 Work authorized under this section will be measured as provided in 109.01; however, when such work falls within the specifications for another contract item, the work will be measured according to the method of measurement for that contract item.

Amend 5.1 to read:

- **5.1** Payment for work authorized under this item will be made on a dollar basis according to 109.04 method C or D.
- **5.1.1** The cost of construction and maintenance of temporary erosion and pollution control devices not under a separate contract item will be included for payment under this item.

Amend 5.2 to read:

- **5.2** Payment for the following work will not be allowed under this item.
- **5.2.1** The temporary diversion of water during culvert construction and the dewatering, pumping and discharge of water at cofferdams and bridge sites shall be subsidiary to the pertinent contract item. However, settlement basins, detention ponds or other approved sediment treatment measures required will be included for payment under this item unless otherwise shown on the plans.
- **5.2.2** Temporary erosion and pollution control measures required due to the Contractor's failure to install permanent controls as a part of the scheduled work, negligence, carelessness or type of operation outside the generally accepted standard construction practices within the State, shall be at the Contractor's expense. Also temporary erosion and pollution control measures required at off-site areas including, but not limited to, haul roads, equipment and material storage sites, material pits, material processing sites and disposal areas shall be at the Contractor's expense.
- **5.2.3** Erosion control measures including dust control required for stockpiles of materials subject to wind or water erosion shall be at the expense of the Contractor.
- **5.2.4** Repair and maintenance of damaged or failed slopes, until project acceptance as stated in section 104.13 shall be at the expense of the Contractor.

Amend Pay item and unit to read:

699 Temporary Project Erosion and Water Pollution Control

Dollar