



# Information Report

NEW HAMPTON - ASHLAND

41674

X-A004(713)

County: BELKNAP, GRAFTON  
 Date Bids Open: 1/31/2019  
 Scope of Work: Pavement preservation with associated evaluations of drainage and guardrail I-93  
 MM 67.6 to 75.0  
 Location: I-93  
 Completion Date: 8/23/2019  
 Proposal Guarantee: 5% of bid amount

Item Number	Item Description	Unit	Estimated Quantity
<b>NEW HAMPTON - ASHLAND 41674</b>			
<b>19234B -New Hampton-Ashland-I-93</b>			
403.11002	HOT BITUMINOUS PAVEMENT, MACHINE METHOD (QC/QA TIER 2)	TON	12,500.00
403.4	MATERIAL TRANSFER VEHICLE (MTV)	TON	23,050.00
403.6	PAVEMENT JOINT ADHESIVE	LF	142,300.00
410.22	ASPHALT EMULSION FOR TACK COAT	GAL	7,150.00
413.6	CRACK FILL PRIOR TO THIN LIFT OVERLAY	LB	25,000.00
417.	COLD PLANING BITUMINOUS SURFACES	SY	116,400.00
417.21	MICRO-MILLING BITUMINOUS SURFACES	SY	150,000.00
419.13	BONDED WEARING COURSE, TYPE C	TON	10,900.00
559.41	ASPHALTIC PLUG FOR CRACK CONTROL (F)	LF	316.00
559.412	REPAIR ASPHALTIC PLUG EXPANSION JOINT (F)	LF	594.00
618.61	UNIFORMED OFFICERS WITH VEHICLE	\$	30,000.00
618.7	FLAGGERS	HR	150.00
619.1	MAINTENANCE OF TRAFFIC	U	1.00
619.25	PORTABLE CHANGEABLE MESSAGE SIGN	U	2.00
619.253	PORTABLE CHANGEABLE MESSAGE SIGN (UNIT WEEK)	UWK	5.00

619.27	TRAILER-MOUNTED SPEED LIMIT SIGN	U	2.00
619.279	AUTOMATED TRAILER-MOUNTED SPEED LIMIT SIGN	U	2.00
632.0106	RETROREFLECTIVE PAINT PAVE. MARKING, 6" LINE	LF	369,700.00
632.01069	SHORT TERM PAVEMENT MARKINGS, 6" LINE	LF	188,500.00
632.1104	PREFORMED RETROREFLECTIVE TAPE, TYPE I (REMOVABLE) 4" LINE	LF	16,200.00
632.3106	RETROREFLECT. THERMOPLAS. PAVE. MARKING, 6" LINE	LF	4,000.00
632.3112	RETROREFLECT. THERMOPLAS. PAVE. MARKING, 12" LINE	LF	3,100.00
632.3118	RETROREFLECT. THERMOPLAS. PAVE. MARKING, 18" LINE	LF	18.00
632.911	OBLITERATE PAVE. MARKING LINE, 12" WIDE & UNDER	LF	30,600.00
632.912	OBLITERATE PAVE. MARKING LINE, OVER 12" WIDE	LF	16.00
692.	MOBILIZATION	U	1.00
698.13	FIELD OFFICE TYPE C	MON	5.00
1006.23	SPECIAL WORK - EXTRACTED AND RECOVERED ASPHALT BINDER TESTING	\$	3,100.00
1010.15	FUEL ADJUSTMENT	\$	39,000.00
1010.2	ASPHALT CEMENT ADJUSTMENT	\$	35,000.00
1010.3	QUALITY CONTROL QUALITY ASSURANCE (QC/QA) ASPHALT	\$	44,169.00
<b>19234B -New Hampton- Ashland- I-93 - ITS</b>			
614.331	3" STEEL CONDUIT	LF	80.00
614.523	MOLDED PULL BOX 17"X30"	EA	2.00
614.73114	3" PVC CONDUIT, SCHEDULE 40	LF	130.00
645.42	TEMPORARY SLOPE MATTING TYPE B (WILDLIFE FRIENDLY)	SY	30.00
645.512	COMPOST SOCK FOR PERIMETER BERM	LF	200.00
645.531	SILT FENCE	LF	200.00
646.41	TURF ESTABLISHMENT WITH MULCH, TACKIFIERS AND HUMUS	SY	100.00
677.3101	WIRELESS COMMUNICATIONS EQUIPMENT	U	1.00
677.41001	CLOSED CIRCUIT TELEVISION (CCTV) SYSTEM FOUNDATION	U	1.00
677.4101	CCTV SYSTEM	U	1.00

677.54201	POLE MOUNTED ITS EQUIPMENT CABINET	U	1.00
677.5811	100 MBPS ETHERNET SWITCH	EA	1.00
677.6301	METER AND DISCONNECT PEDESTAL	U	1.00
677.6302	METER AND DISCONNECT PEDESTAL	U	1.00
677.64	UNINTERRUPTABLE POWER SUPPLY (UPS)	EA	1.00
677.9306	3-CONDUCTOR #6 AWG CABLE	LF	250.00
699.	MISCELLANEOUS TEMPORARY EROSION AND SEDIMENT CONTROL	\$	5,000.00
1008.928	ALTERATIONS AND ADDITIONS AS NEEDED - WIRELESS COMMUNICATIONS EQUIPMENT (SALVAGE TO DEPARTMENT)	\$	400.00
1010.15	FUEL ADJUSTMENT	\$	1,000.00