STATE OF NEW HAMPSHIRE
INTRA-DEPARTMENT COMMUNICATION

FROM Matt Urban
Wetlands Program Manager

DATE June 13, 2016
AT (OFFICE) Bureau of Environment

SUBJECT Wetland Bureau Permit # 2016-00513
Washington, 29761

TO Steve Johnson, Bureau of Bridge Maintenance (271-3667),

Forwarded herewith, for your files and further use as appropriate, is a copy of the subject permit as approved by the Wetlands Bureau and the Water Division on 05/31/2016.

Please note specific conditions on permit.

TERRAIN ALTERATION
Note that the non-site specific permit (RSA 485-A: 17 "Terrain Alteration") is part of this Wetlands Bureau Permit.

WATER QUALITY CERTIFICATION
- ☒ This permit covers the project's consideration for Water Quality protection and no further action is required by this office.
- ☐ This permit does not cover the Water Quality protection for this project. However, a Water Quality Permit will be obtained for this project.

CORPS PERMIT STATUS
- ☐ No Corps Jurisdiction
- ☐ SPGP (Minimum Impact) - No waiting period; no Corps approval required
- ☐ SPGP (Minor Impact)-Wait 30 days from NHWB issuance date; no written approval from Corps required
- ☒ SPGP (Major Impact)-Wait 30 days from NHWB issuance date; written approval from Corps required
- ☐ Emergency - No waiting period; No written approval from Corps required
- ☐ Amendment - No waiting period; No written approval from Corps required
- ☐ Corps Individual Permit Required

COASTAL ZONE MANAGEMENT (CZM) STATUS
- ☒ Outside of Coastal Zone-consistency finding not necessary from OSP
- ☐ Within Coastal Zone (Non-Federal Action)-consistency finding not necessary form OSP
- ☐ Within Coastal Zone (Federal Action)-if covered by SPGP, or no Corps' jurisdiction, consistency finding is automatic from OSP
- ☐ Within Coastal Zone (Federal Action)-if individual Corps permit, written consistency finding is necessary from OSP

EROSION CONTROL PLAN STATUS
- ☐ Erosion Control Plan Required; Submit Erosion Control Plan to DES Wetlands Bureau

If you have any questions, please call 271-3226.

MRU:mru
Encl.
BOE Original
Anthony Weatherbee

S:\Environment\PROJECTS\WASHINGTON\29761\Permit Distribution - Bridge Maint.doc

The State of New Hampshire

DEPARTMENT OF ENVIRONMENTAL SERVICES

Thomas S. Burack, Commissioner

RECEIVED
BUREAU OF ENVIRONMENT
JUN 03 2016
NH DEPARTMENT OF TRANSPORTATION

WETLANDS AND NON-SITE SPECIFIC PERMIT 2016-00513

Permittee: NH Dept. of Transportation
PO Box 483
Concord, NH 03302-0483

Project Location: NH Route 31, Washington
Washington Tax Map/Lot No. ROW / ROW

Waterbody: Shedd Brook

NOTE--
CONDITIONS

APPROVAL DATE: 05/31/2016 **EXPIRATION DATE: 05/31/2021**

Based upon review of the above referenced application, in accordance with RSA 482-A and RSA 485-A:17, a Wetlands Permit and Non-Site Specific Permit was issued. This permit shall not be considered valid unless signed as specified below.

PERMIT DESCRIPTION: Rehabilitate the bridge that has a 10 ft. clear span and a 28 ft. 4 inch deck width by replacing the concrete deck, repair the concrete substructure and toewall and place riprap impacting 2,244 sq. ft. (1,500 sq. ft. temporary) of riverine wetlands. NHDOT project #29761

THIS APPROVAL IS SUBJECT TO THE FOLLOWING PROJECT SPECIFIC CONDITIONS:

1. All work shall be in accordance with plans by NHDOT Bureau of Bridge Maintenance dated June 17, 2015 as received by the NH Department of Environmental Services (DES) on Mar. 1, 2016.
2. Dredged material shall be placed out of the DES Wetlands Bureau jurisdiction.
3. Unconfined work within the stream, exclusive of work associated with installation of a cofferdam, shall be done during periods of low flow.
4. Cofferdams shall not be installed during periods of high flow, whether due to seasonal runoff or precipitation. Once a cofferdam is fully effective, confined work can proceed without restriction.
5. Prior to commencing work on a substructure located within surface waters, a cofferdam shall be constructed to isolate the substructure work area from the surface waters.
6. Temporary cofferdams shall be entirely removed immediately following construction.
7. Construction equipment shall not be located within surface waters.
8. Discharge from dewatering of work areas shall be to sediment basins that are: a) located in uplands; b) lined with hay bales or other acceptable sediment trapping liners; and c) set back as far as possible from wetlands and surface waters, in all cases with a minimum of 20 ft. of undisturbed vegetated buffer.
9. Appropriate turbidity controls shall be installed prior to construction, shall be maintained during construction such that no turbidity escapes the immediate dredge area, and shall remain until suspended particles have settled and the water at the work site has returned to normal clarity.
10. Within three days of the last activity in an area, all exposed soil areas, where construction activities are complete, shall be stabilized by seeding and mulching during the growing season, or if not within the growing season, by mulching with tack on slopes steeper than 3:1 or netting /matting and pinning on slopes steeper than 2:1.
11. Where construction activities have been temporarily suspended within the growing season, all exposed soil areas shall be stabilized within 14 days by seeding and mulching or if temporarily suspended outside the growing season, all exposed areas shall be stabilized within 14 days by mulching, mulching with tack on slopes steeper than 3:1 and stabilized by matting and pinning on slopes steeper than 2:1.

12. The contractor responsible for completion of the work shall utilize techniques described in the New Hampshire Stormwater Manual, Volume 3, Erosion and Sediment Controls During Construction (December 2008).
13. Extreme precautions to be taken within riparian areas to limit unnecessary removal of vegetation during road construction and areas cleared of vegetation to be revegetated as quickly as possible.
14. There shall be no further alteration to wetlands or surface waters without amendment of this permit.
15. Standard precautions shall be taken to prevent import or transport of soil or seed stock from nuisance, invading species such as purple loosestrife or Phragmites.
16. The impacts associated with the temporary work shall be restored immediately following construction.

GENERAL CONDITIONS THAT APPLY TO ALL DES WETLANDS PERMITS:

1. A copy of this permit shall be posted on site during construction in a prominent location visible to inspecting personnel;
2. This permit does not convey a property right, nor authorize any injury to property of others, nor invasion of rights of others;
3. The Wetlands Bureau shall be notified upon completion of work;
4. This permit does not relieve the applicant from the obligation to obtain other local, state or federal permits, and/or consult with other agencies as may be required (including US EPA, US Army Corps of Engineers, NH Department of Transportation, NH Division of Historical Resources (NH Department of Cultural Resources), NHDES-Alteration of Terrain, etc.);
5. Transfer of this permit to a new owner shall require notification to and approval by DES;
6. This project has been screened for potential impacts to **known** occurrences of rare species and exemplary natural communities in the immediate area. Since many areas have never been surveyed, or have received only cursory inventories, unidentified sensitive species or communities may be present. This permit does not absolve the permittee from due diligence in regard to state, local or federal laws regarding such communities or species.
7. Review enclosed sheet for status of the US Army Corps of Engineers' federal wetlands permit.

APPROVED: Gino Infascelli
Gino Infascelli
DES Wetlands Bureau

==========

BY SIGNING BELOW I HEREBY CERTIFY THAT I HAVE FULLY READ THIS PERMIT AND AGREE TO ABIDE BY ALL PERMIT CONDITIONS.

OWNER'S SIGNATURE (required)

CONTRACTOR'S SIGNATURE (required)

The State of New Hampshire
DEPARTMENT OF ENVIRONMENTAL SERVICES

Thomas S. Burack, Commissioner

NOTICE TO RECIPIENTS OF MAJOR IMPACT N.H. WETLANDS PERMITS

Your permit was approved by the New Hampshire Wetlands Bureau as a major impact project, and your project will be reviewed by the U.S. Army Corps. Of Engineers for possible approval under the Army Corps. New Hampshire State Programmatic General Permit- SPGP. The Army Corps. will notify you within thirty (30) days as to whether you qualify.

*********NO WORK SHOULD BE DONE IN********
***********WETLANDS UNTIL YOU RECEIVE THAT NOTICE*************

IF YOU DO NOT HEAR FROM THE ARMY CORPS WITHIN THIRTY (30) DAYS, YOU SHOULD CALL THEM AT 1-800-343-4789.

****

CC: U.S. ARMY CORPS. OF ENGINEERS

DES Web site: **www.des.nh.gov**
P.O. Box 95, 29 Hazen Drive, Concord, New Hampshire 03302-0095
Telephone: (603) 271-2147 • Fax: (603) 271-6588 • TDD Access: Relay NH 1-800-735-2964