

07/27/20

SSD: 04/14/16, 05/11/16, 06/02/16, 09/15/16, 01/04/17, 02/01/17, 04/06/17, 06/09/17, 04/02/18, 05/21/18,
07/06/18, 11/07/18**SPECIAL ATTENTION****THIS PROJECT IS TO BE BID AND CONSTRUCTED UNDER THE
2016 STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION****NOTICE OF SUPPLEMENTAL SPECIFICATIONS**

The following table is a list of all of the Supplemental Specifications that have been adopted as additions or revisions to the *Standard Specifications for Road and Bridge Construction*, **March 2016** Edition as of the date of this Proposal. The Bidder is responsible to examine each item to determine its effect, if any, upon the Contract.

Note: Due to the limited scope of some projects, not all Supplemental Specifications will be included in all Proposals. All Supplemental Specifications are available on-line: www.nh.gov/dot/org/projectdevelopment/highwaydesign/specifications/.

Section	Description	Revision	Previous Revision Date	Current Revision Date
<i>DIVISION 100</i>				
101	Definitions and Terms	101.79 – Revises Frequency of QPL Updates (06/06/17) 101.116-119 – Revises Definitions of Weather Days and Working Days (04/02/18)	06/06/17	04/02/18
106.04	Qualified Products List	Revises Frequency of Updates		06/06/17
107.01	Legal Relations and Responsibility to Public	107.01 – Revises References to DES Rules and Regulations		07/06/18
108.09	Prosecution and Progress	108.09 – Amends the Requirements for Liquidated Damages		07/06/18
109.04	Differing Site Conditions, Changes and Extra Work	Revises Rental Rate Blue Book Online Requirements (04/02/18)	01/06/12	04/02/18
<i>DIVISION 200</i>				
211.3.4	Vibration Monitoring	Adds reference to pre- and post-construction survey requirements		04/05/17
<i>DIVISION 300</i>				
<i>DIVISION 400</i>				
401	Plant Mix Pavements - General	2.5.1 - Adds winter binder to the design control points (04/05/17) 2.10 – No greater than 1% TRB (06/06/17) 3.4.1 – Revises Cold Feeder Requirements (07/06/18)	07/06/18	11/07/18

		<p>3.4.7.1 – Revises Recycled Materials Weighing Procedures (07/06/18)</p> <p>3.4.11 - 3.4.15 – Describes Introduction of Recycled Materials at a Batch Plant and Controls Minimum Dry Time for Recycled Aggregates (07/06/18)</p> <p>3.5.2 & 3.5.2.1 – Revises Recycled Materials Requirements (07/06/18)</p> <p>3.10.10.1 – Removes penalty for failing tack (06/06/17)</p> <p>3.12 – Allows a reduction in use of pneumatic-tired rollers (06/06/17)</p> <p>3.17.1.3 - Revise NETTCP QA Technologist requirements (11/07/18)</p> <p>3.17.3.1.1 – Revises HMA gradation specification limits, completes addition of winter binder, removes allowance for Aim change after two sub-lots (06/06/17)</p> <p>4.1.1 – Removes reference to Night Items (06/06/17)</p>		
403.1.3	Pavement Item Numbers	<p>Removes all references to Night Items and removes “percent wear” items. (06/06/17)</p> <p>Total overhaul of Item Numbers and Descriptions to allow for type of lift in item description. (07/27/20)</p>	06/06/17	07/27/20
410	Bituminous Surface Treatment	<p>2.1- Adopts new AASHTO Specifications for Emulsions (04/13/16)</p> <p>3.4.1.1 – Revises pavement conditions, application rate for tack (01/04/17)</p> <p>2.1.1, 2.1.2, 3.2, 3.3, 3.4 – Identifies tack sampling and penalties for non-conformance (06/06/17)</p> <p>3.2 & 3.5.2 – Amends Distribution Equipment and Initiates an Annual Tack Truck Inspection Program (07/06/18)</p>	06/06/17	07/06/18
411.3.5.5	Pneumatic Tired Roller	<p>3.5.5 – Requires the use of pneumatic tired rollers on all Section 411 paving (06/06/17).</p> <p>5.1.1 – Ensures Tack Used for PMST and Leveling Course is a Pay Item (07/06/18)</p>	04/02/18	07/06/18

Removes Pay Items (04/02/18)				
417	Rumble Strip Inlay	2.1 & 3.7 – Specifies PMST as the asphalt inlay to fill in rumble strips		04/02/18
<i>DIVISION 500</i>				
520	Portland Cement Concrete	3.8.1.1 – Revises the acceptable concrete delivery temp to 90° F (04/02/18) 3.1.6.2.1.2 A - Revise NETTCP QA Technologist requirements (11/07/18)	04/02/18	11/07/18
530	Waterproofing Concrete Surfaces	Deletes Section 530		05/21/18
538	Barrier Membrane	3.3.5 – Updates the laydown temperature range.		09/15/16
563	Bridge Fence	2.8 – Allows aluminum ties for attaching bridge fence		09/15/16
568	Structural Timber	2.2, 3.4.4 & 3.4.5 – Adds specific references to AWP Standards & wooden piles		04/02/18
582	Preformed Joint Filler	2.4 – Revises Preformed Joint Filler Requirements		04/02/18
<i>DIVISION 600</i>				
603	Plastic Pipe	2.3, 2.6 & 2.7 – Updated to include Polypropylene Pipe as well as associated UV Requirements (04/13/16) 2.13 – Adds Contractor's Option (06/02/16)	04/13/16	06/02/16
605	Plastic Pipe	2.1 & 2.2 – Updated to include Polypropylene Pipe		04/13/16
606	Guardrail	2.2 – Adds specific references to AWP Standards & wooden piles		04/02/18
608	Detectable Warning Devices	2.6 – Updates Detectable Warning Device Requirements		04/02/18
609	Curbs	2.4.1.1 – Allows the substitution of PG 76-28 binder in lieu of fibers		04/02/18
615	Cofferdam for Sign Installation	5.1.5 – Revises payment for sheeting and shoring for sign structures		04/02/18

645	Erosion Control	<p>1.1 – Matting Section Revised and Pay Items Revised (04/02/18)</p> <p>1.1 – ‘Stabilization’ changed to ‘matting’ (02/01/17)</p> <p>Incorporates BFM, FRM and SMM into the Standard Specs (07/06/18)</p> <p>1.2.1 – Add Erosion Control Plans to furnish for SWPPP (11/07/18)</p> <p>3.1.5 – Update construction dates for allowable area of exposed, unstabilized soil (11/07/18)</p>	07/06/18	11/07/18
<i>DIVISION 700</i>				
702	Bituminous Materials	<p>Amends Table 702-1 & 702-2 (04/13/16)</p> <p>Amends Tables, and Adds test method (05/11/16)</p>	04/13/16	05/11/16
