Laconia 16144


US Route 3 over New Hampshire Railroad (Br. No. 131/154) Public Informational Meeting







Project Location Map







Looking North

New Hampshire











West Abutment



East Abutment



WEIRS IS FACH

Retaining Wall – From Above












Looking West up Endicott Street (US Route 3)

















Looking South down Channel Lane from US 3

















Existing Bridge Facts

- Bridge was put on the State's Red List in 2009, #40 on the 2015 Bridge Priority List
- Federal Sufficiency Rating (FSR) of 32.7 out of 100
- Carries Approximately 13,000 Vehicles per day in 2011 (5% trucks), Posted speed 30 mph,
 - April last month before traffic significantly increases
- Rail service May to November

Superstructure

- Is a Cast-In-Place (CIP) Concrete Slab constructed in 1933
- It's a 23' to 32 'long single span which carries US Route 3 over NHRR
- The narrowest roadway width is 27 'between curbs, 7' wide sidewalk along the north side of the bridge
- The railroad vertical clearance is 17.5 'from top of rail to bottom of slab


Substructure

- Is primarily made up of split granite block abutments, built prior to 1933 (there are no existing records of their construction)
- In 1933 the abutments were widened with mass concrete along with a wingwall along Lakeside Ave.






Existing Bridge Details








Existing Bridge Facts







Inspection Photos



Underside of Bridge Deck – Exposed Reinforcement





Inspection Photos



East Abutment
Mortared Joints in Disrepair, Stone Stable With No Signs of Shifting





Inspection Photos



Retaining Wall – Cracking





Summary of Inspection

Based on Visual Inspection and Material Testing:

• **Superstructure:** Poor condition, needs Replacement

• Abutments: Fair Condition, can be Rehabilitated

• Wingwalls: Fair Condition, can be Rehabilitated





Design Considerations

- Narrow roadway shoulders over bridge (not easily widened without increasing bridge width)
- Line of sight & obstructions (concrete rail)
- Many Utilities (move prior to construction)
- Close proximity to intersections
 - Lakeside Avenue
 - Channel Lane
 - Endicott Rock Park Drive
- Located in Tourist Area
 - Weirs Beach
 - Other Attractions
- NHRR with 17.5 'clearance
- Detour Length
- Traffic volumes







Bridge Improvement Options

Superstructure Replacement Options

 \triangleright Steel beams with a concrete deck \Rightarrow Deep structure depth, clearance issues

 \triangleright Cast-In-Place Concrete Slab \Rightarrow Slow to Construct

 \triangleright Precast-Prestressed Voided Slabs \Rightarrow Accelerate Schedule Advantages

Bridge Rail Options

 \triangleright Concrete Bridge Railing \Rightarrow Line of Site issues, Safety Concerns

> T4 Bridge Railing => Accelerate Schedule Advantages


Substructure Options

- ➤ Do nothing ⇒ Deterioration, needs to be addressed
- ➤ Complete replacement ⇒ Delays, Cost, Permits, ROW, Substructure still Viable
- > Repair Existing Abutment => Existing Abutments are Stable & can be Rehabilitated





Bridge Improvement Option (Proposed Bridge)




Cast-In-Place (CIP) Very Similar





Utilities

- Public Service of NH
 - 3 phase 35KV
 - 2 3 phase 4KV
- Fair Point Communications
 - Nine 4" ducts in sidewalk
- Metrocast (CATV)
- Fire Alarm Tech
- Laconia Dept of Public Works (sewer)
- Gilford Gravity Sewer & Force Main







Cultural Resources



Historic Research is Ongoing





Natural Resources


- Wetlands (swale by railroad)
- Hazardous Material (potential)
- Invasive Species (present)
- Air and Noise (no long-term impacts anticipated)
- Section 4(F) (Endicott State Park)
 (Historic Properties, Public Parks,
 Fish & Waterfowl / Wildlife refuge)
- Section 6(F) (Endicott State Park)
 (Property purchased with Federal Funds)







Right-of-Way & Abutters to Project



ROW currently under research Temporary easements will likely be needed





Traffic Control - Two Alternatives

- 1. Phased Construction: Alternating One-Way with Temporary Signals
- 2. Bridge Closure / Accelerated: Detour Traffic





Traffic Control Alternative #1 (Phased Construction)

- Alternating One-Lane two-directional traffic via Signal Control
- Difficult due to narrow width of Structure and Close Proximity of Intersections
- Estimated 120 day Construction Time due to Site Constraints and Building a Bridge in Three Phases
- Cost approximately 25% More Than Bridge Closure Option





Traffic Control Alternative #1 (Phased Construction)

Existing


Phase 1

Phase 2

Phase 3

Final








Traffic Control Alternative #2 (Closed/Accelerated Construction)

- Accelerated Options
- Emergency Response Coordination Required
- 30 Day (Accelerated) Construction Lengths (April timeframe?)
- Most Economical
- Accelerated Option Recommended

Existing


New / Proposed







Traffic Control Alternative (Detour Route)







Potential Emergency Vehicle Response Route (Closed Option)










Potential Emergency Vehicle Response Route (Closed Option)



Channel Lane Intersection



Non-public Access Rd





Hillard Rd

Intersection

Next Steps and Schedule

- Incorporate City Officials & Public's comments
- Meet with City to review recommended solutions (Fall of 2015)
- Work with ROW, Cultural & Natural Resource Agencies
- Develop Contract Plans by End of 2016
- Advertise fall of 2019 (if funds are available)
- Construction fall of 2019 to spring 2020 (closure likely would be April)
- Estimated Construction Cost \$1,500,000 based on Superstructure Replacement with Accelerated Construction and Bridge Closure





Concerns, Comments, & Questions







Your Input is Needed On

- Emergency Response Routes
- Mutual Aid from/to Adjacent Towns
- School Bus Routes
- Closure vs Phased Construction
- Time of Year for Closure (does April work?)
- Concerns with Historic Resources
- Tourism Concerns
- Post Office Access for Pedestrians
- Railing Treatment Along Wing Wall
- Other Concerns





Table of Contents

| (1 slide) |
|------------|
| (1 slide) |
| (7 slides) |
| (3 slides) |
| (4 slides) |
| (1 slide) |
| (2 slides) |
| (4 slides) |
| (6 slides) |
| (1 slide) |
| (1 slide) |
| (1 slide) |
| |



