

**PORTSMOUTH-KITTERY  
16189B**

September 18, 2020

**SPECIAL PROVISION****AMENDMENT TO SECTION 202 -- REMOVAL OF STRUCTURES  
AND OBSTRUCTIONS****Item 202.8350\_ – Remove and Salvage Wireless Antenna**

*This special provision provides for the removal of existing Intelligent Transportation System (ITS) devices and neither amends nor modifies the provision of this section except as noted below:*

**Description**

**Add** after 1.4:

**1.5** This work shall consist of removal and salvage of existing Wireless Antenna as indicated in the Plans and Project Documents.

**1.5.1** This work shall consist of disconnecting, removing, and salvaging existing wireless communication systems, including antennas and control equipment within the Project area that will be replaced or abandoned. The wireless equipment shall be salvaged to the maintaining Owner.

**Construction Requirements**

**Add** after 3.9:

**3.10 Removal of Wireless Communications Equipment.**

**3.10.1** The Contractor shall host a meeting with the Contract Administrator, the Construction Quality Manager, the Owners, and any equipment subcontractors not less than fourteen (14) days prior to the start of wireless devices removal.

**3.10.1.1** The Contractor shall coordinate with the Owners and the Contract Administrator for the operations required to remove the equipment from its existing supports and mountings and to verify the location that the equipment will be delivered to for salvaging.

**3.10.2** The Contractor shall deenergize and disconnect the existing wireless communications antenna from its power source and disconnect the communications equipment from all its applicable connections, including any specific ground wiring and cabling.

09/18/2020

Page 2 of 2

**3.10.3** The wireless communications antenna to be removed shall be removed by the Contractor without damaging or impeding the operations of any adjacent ITS systems, bridges, or highway operations.

**3.10.4** The Contractor shall be responsible for any operational equipment, hardware, conduits or cabling that are damaged during the removal. Any damaged equipment shall be repaired or replaced by the Contractor to the satisfaction of the Owners at no additional cost to the Owners.

### **Method of Measurement**

**Add** after 4.6.1:

**4.7** Remove and salvage wireless antenna will be measured for payment as a unit. Where more than one unit is specified in the contract, separate item numbers will appear for each separate and complete unit removed.

### **Basis of Payment**

**Add** after 5.9:

**5.10** The accepted quantity for Remove and Salvage Wireless Antenna will be paid for at the contract unit price complete. A complete unit of remove and salvage shall mean all work necessary for coordination with the Bureau of TSMO, the TMC and the Contract Administrator, deenergizing and disconnecting all power and communication cabling and connections to the antenna, salvaging and transporting the equipment to a designated location (within 100 miles of Kittery, Maine), and all labor, tools, transportation, coordination, documentation, and incidentals necessary to complete the work.

**Add to Pay Items and Units:**

202.8350_	Remove and Salvage Wireless Antenna	Unit
-----------	-------------------------------------	------