# Springfield 20509 Georges Mills Road Over Star Lake Outlet Public Information Meeting



February 26, 2018



# **Project Location**





# **Project Location**








Georges Mills Road Looking North






Fisher Corner Road





Intersection with Fisher Corner



Intersection with Stryker Road





**Downstream Elevation** 



**Upstream Elevation** 




# **Existing Bridge**

- Twin 5-foot diameter buried corrugated metal pipes built in 1951
- Stone headwalls and wingwalls
- NHDOT inspection report lists the culvert in "poor" condition
- Inadequate hydraulic capacity
- On the NHDOT Red List since 2008
- NHDOT Bridge priority #122
- Carries approximately 1,700 vehicles per day with 7.4% trucks



# **Bridge Components**






# **Inspection Photos**



Separation of Pipe Sections



Holes Through Pipe



# **Inspection Photos**



Pipe Inlets



#### **Natural and Cultural Resources**

- Project has NEPA and Section 106 obligations for potential Natural & Cultural Resource Impacts
  - coordination with Resource Agencies is ongoing
- No Anticipated Historic Impacts
- Interested persons or organizations may request "Consulting Party" status from FHWA
- Anticipate Impacts to Star Lake Outlet that will Require Permitting



# **Design Considerations**

- Structural issues
- Hydraulics
- Environmental permitting
- Bridge proximity to intersection
- Truck turning movements
- Access to businesses, and residences
- Roadway and drainage improvements
- Overhead utility lines
- Maintenance of traffic



# Traffic Control Alternatives During Construction

 Maintain a single lane of alternating oneway traffic (with temporary signals),

or

 Close bridge and detour traffic, use accelerated bridge construction techniques




# Traffic Control Alternatives During Construction

Maintain Single lane of alternating one-way traffic

- Phased Construction, construct one half of bridge at a time
- Maintain one lane alternating traffic on Georges Mills Road, temporary traffic signals
- Maintain turning traffic onto Stryker Road and Fisher Corner Road




#### **Phased Construction**



**Phase One Construction** 



#### **Phased Construction**



**Phase Two Construction** 





#### **Phased Construction**

- Requires an additional 30-feet of structure length
- Not all turning movements can be maintained
- Less safety for construction personnel and motorists
- Increased environmental impacts
- Increased ROW impacts
- Increased construction costs
- Slower construction
- 14 weeks for bridge construction, followed by two weeks of roadway construction



#### **Traffic Control Alternatives**

#### Closed Bridge During Construction

- Requires detour
- Requires coordination with emergency response providers
- Utilize accelerated bridge construction techniques to limit closure duration




# Closure Advantages

- Most cost effective
- Minimizes ROW impacts
- Minimizes environmental impacts
- Safer for construction personnel and motorists
- Less time to construct
- 3 week closure for box culvert alternative or 4 week closure for rigid frame alternative
- Followed by two weeks of roadway construction




# **Bridge Closure**






# **Signed Detour**





# **Signed Detour**






# **Bridge Structure Alternatives**

- Rehabilitation not feasible due to poor condition, and hydraulic requirements
- Replacement options:
  - Precast Concrete Box Culvert
  - Precast Concrete Rigid Frame



# **Bridge Alternatives**





#### **Precast Box Culvert**

Buried structure


20-foot span

Simulated Stream bed material

 Difficult environmental permitting process, needs to follow "alternative design" process

 Least expensive alternative


Quickest to construct





# **Precast Rigid Frame**

- Buried structure
- 31-foot span
- Precast footings
- Fully compliant with NHDES stream crossing rules







# **ROW Impacts**





### **Next Steps**

- Complete Bridge Evaluations
- 2<sup>nd</sup> Public Informational Meeting
- Develop Preliminary Plans
- Cultural/Historic Coordination
- Environmental Permitting
- Utility Coordination
- Right-of-Way Process
- Develop Contract Plans and Documents



# **Project Schedule/Cost Summary**

- Advertise Project October 2019
- Construction Starts Spring 2020
- Estimated Construction Cost
  - 20' Box Culvert (Closure/Detour) \$1.1 Million 3 week closure/bridge construction
  - 31' Frame (Closure/Detour) \$1.5 Million 4 week closure/bridge construction
  - 31' Frame (Phased Construction) \$2.2 Million

    14 weeks bridge construction

# Your Input Is Needed

- Emergency Response Routes
- Mutual Aid from Adjacent Towns
- School Schedule and Bus Routes
- Special Town Events
- History of Flooding
- Intersection Concerns
- Bridge work during low flow time of year, late June, July, August - Concerns
- Other Questions/Concerns



# **Thank You For Attending**



